

Robby One – Initial System Testing Customer Readiness Guidelines

Electrical Preparation

Confirm the electrical connection for the Robby One is fully installed and is ready for use. The power supply must match the electrical requirement and specifications for the unit.

For safety purposes, the electrical power to the outlet or breaker connected to Robby One **MUST BE TURNED OFF** prior to the arrival of the installation team.

Water Line Preparation

Confirm the water supply line has been installed, and the connection point is accessible for the service team. The **main water valve supplying to the connection point should be turned OFF**.

Test Cooking Program Preparation

Recommended Customers to provide 1 - 2 simple recipes for the initial system test. Suggested options include simple stir-fry dishes such as **fried rice, noodles, or sautéed vegetables**.

When providing a recipe, ensure the **kitchen or the test site is properly stocked with all required ingredients prior to the Service Team scheduled date**.

Robby One Ingredient Bin Configuration:

The Robby One ingredient dispensing system includes:

- **5 dry seasoning bins** (for spices, salt, sugar, seasoning powders, etc.)
- **6 small liquid ingredient bins** (for sauces or liquid flavorings)
- **1 cornstarch slurry bin** (for slurry mixtures or thickening agents)

Ensure the required ingredients are available at the time of testing and training for your recipes to be ready for testing.

For the RoboOp365 team to provide the testing recipes, an ingredient list shall be furnished within 3 days in advance for your kitchen service team to prepare all necessary items before system testing.

Cooking Drum Seasoning

Please ensure a **minimum of 24 oz Grapeseed oil** is available and ready for system testing at the

designated site for the initial seasoning process. **Grapeseed oil** is recommended due to its neutral flavor and high smoke point.
